



Final Subdivision Plat Application

Delaware County, Ohio

(for unincorporated areas only)

RPC Number 07-22 . 2
 Sec. 2 Ph. Pt.

FINAL PLATS CANNOT BE SUBMITTED UNLESS A DRAFT VERSION HAS BEEN REVIEWED BY DCRPC and other AGENCIES

PROJECT	Berlin Bluffs Section 2	(circle one) <u>Residential</u> Commercial
TOWNSHIP	Berlin	

APPLICANT/ CONTACT	Name: Pulte Homes of Ohio, LLC	Phone: (614) 376-1018
	Address: 475 Metro Place South, Suite 200	E-mail: matthew.callahan@pulte.com
	City, State, Zip: Columbus, Ohio 43017	

PROPERTY OWNER	Name: Pulte Homes of Ohio, LLC	Phone: (614) 376-1018
	Address: 2785 Cheshire Rd	E-mail: matthew.callahan@pulte.com
	City, State, Zip: Delaware, Ohio 43015	

SURVEYOR/ ENGINEER	Name: Kevin Kershner	Phone: (614) 472-8963
	Address: 7965 North High Street, Suite 200	E-mail: kevin.kershner@kimley-horn.com
	City, State, Zip: Columbus, Ohio 43245	

DETAILS	Total Lots: 31 Lots	Buildable lots: 29 Lots
	Total Acreage: 16.90 AC	Open Space Acreage: 4.75 AC

SUBMISSION REQUIREMENTS (Sub. Regs. Section 205.01)	Date the Preliminary Plan was approved by RPC (required):
	Date of Draft Plat Review by RPC staff (required):
	Date of Final Engineering Approval by DCEO (required):
	1 (one) Plat signed by subdivider and lien holder, appropriate Zoning, Del-Co, and Health, delivered to the RPC by the deadline.
	1 reduced copy of the Final Plat at 11" x 17".
	PDF of plat, on media or preferably e-mailed to smatlack@co.delaware.oh.us
	For plats including a CAD - 1 copy of CAD Maintenance Agreement
	Fee - \$500 base, then \$110 per build lot, CADs require additional fees; For commercial and multi-family - \$500 base, then \$110 per acre; DCRPC will collect a \$3.00 per buildable lot fee for the Commissioners (Refer to Fee Schedule) \$ <u>3690</u>

 **AGENT FOR OWNER** 4/1/2024
 Owner (or agent for owner) and Date

RECEIVED
APR 01 2024


Delaware County Regional Planning Commission, 1610 State Route 521, P.O. Box 8006
 Delaware, OH 43015 (740) 833-2260

Effective 01/01/24

Del. Co. Regional
 Planning Commission

BERLIN BLUFFS SECTION 2
 STATE OF OHIO, DELAWARE COUNTY, BERLIN TOWNSHIP
 FARM LOT 9, SECTION 3, TOWNSHIP 4, RANGE 18,
 UNITED STATES MILITARY LANDS

R.P.C.
 CASE NO. 07-22.2



SITUATED IN THE STATE OF OHIO, COUNTY OF DELAWARE, TOWNSHIP OF BERLIN, FARM LOT 9, SECTION 3, TOWNSHIP 4, RANGE 18, UNITED STATES MILITARY LANDS, BEING 16.897 ACRES ALL OUT OF THAT ORIGINAL 58.75 ACRE TRACT OF LAND, AS CONVEYED TO PULTE HOMES OF OHIO LLC, A MICHIGAN LIMITED LIABILITY COMPANY, OF RECORD IN O.R. 2010, PG. 217, BEING OF RECORD IN THE RECORDER'S OFFICE, DELAWARE COUNTY, OHIO.

THE UNDERSIGNED, PULTE HOMES OF OHIO LLC, A MICHIGAN LIMITED LIABILITY COMPANY, BY MATTHEW J. CALLAHAN, DIVISION VICE PRESIDENT LAND ACQUISITION, DULY AUTHORIZED IN THE PREMISES, DOES HEREBY CERTIFY THAT THIS PLAT CORRECTLY REPRESENTS "BERLIN BLUFFS SECTION 2", A SUBDIVISION CONTAINING LOTS NUMBERED 3553-3583, AND DOES HEREBY ACCEPT THIS PLAT OF SAME.

EASEMENTS ARE HEREBY RESERVED, IN, OVER AND UNDER AREAS DESIGNATED ON THIS PLAT AS "EASEMENT" (ESMT.), "DRAINAGE EASEMENT" (DRN. ESMT.), "SANITARY EASEMENT" (SAN. ESMT.), AND "UTILITY EASEMENT" (UTIL. ESMT.). EASEMENTS DESIGNATED AS "EASEMENT", "DRAINAGE EASEMENT" OR "UTILITY EASEMENT", PERMIT THE CONSTRUCTION, OPERATION, AND MAINTENANCE OF ALL PUBLIC AND QUASI-PUBLIC UTILITIES ABOVE, BENEATH, AND ON THE SURFACE OF THE GROUND AND, WHERE NECESSARY, FOR THE CONSTRUCTION, OPERATION, AND MAINTENANCE OF SERVICE CONNECTIONS TO ALL ADJACENT LOTS AND LANDS AND FOR STORM WATER DRAINAGE.

EASEMENTS DESIGNATED AS "SANITARY EASEMENT" SHALL MEAN AN EXCLUSIVE SANITARY EASEMENT OVER, THROUGH, UNDER, WITHIN, UPON, AND ACROSS THE AREA DESCRIBED ON THE PLAT, TOGETHER WITH INGRESS AND EGRESS OVER REASONABLE ROUTES ACROSS GRANTOR'S TRACTS THAT ADJOIN THE EASEMENT AREA WHEN EXERCISING THE PURPOSES OF THIS EASEMENT, EXCLUSIVELY FOR CONSTRUCTION, OPERATION AND MAINTENANCE OF PUBLIC AND OR PRIVATE SANITARY SEWERS, SERVICE CONNECTIONS, MANHOLES, FORCE MAINS, VALVES, AND OTHER SANITARY APPURTENANCES. SANITARY EASEMENTS MAY BE CROSSED BY OTHER UTILITIES AS EXPRESSED HEREIN.

IN WITNESS WHEREOF, MATTHEW J. CALLAHAN, DIVISION VICE PRESIDENT LAND ACQUISITION OF PULTE HOMES OF OHIO LLC, A MICHIGAN LIMITED LIABILITY COMPANY HAS CAUSED THIS PLAT TO BE EXECUTED BY THIS DULY AUTHORIZED OFFICE.

THIS 26 DAY OF March 2024.

SIGNED AND ACKNOWLEDGED

PULTE HOMES OF OHIO LLC,
 A MICHIGAN LIMITED LIABILITY COMPANY

IN THE PRESENCE OF:

BY: [Signature]

[Signature]

MATTHEW J. CALLAHAN
 DIVISION VICE PRESIDENT LAND ACQUISITION

[Signature]

STATE OF OHIO
 COUNTY OF DELAWARE:

BEFORE ME, A NOTARY PUBLIC IN AND FOR SAID STATE, PERSONALLY APPEARED MATTHEW J. CALLAHAN, DIVISION VICE PRESIDENT LAND ACQUISITION OF PULTE HOMES OF OHIO LLC, A MICHIGAN LIMITED LIABILITY COMPANY, WHO ACKNOWLEDGED THE SIGNING OF THE FOREGOING INSTRUMENT TO BE HIS VOLUNTARY ACT AND DEED AND THE VOLUNTARY ACT AND DEED OF PULTE HOMES OF OHIO LLC, FOR ITS USES AND PURPOSES EXPRESSED THEREIN.

IN WITNESS THEREOF, I HAVE HEREUNTO SET MY HAND AND AFFIXED MY OFFICIAL SEAL THIS

26 DAY OF March 2024

MY COMMISSION EXPIRES 7.7.26



APPROVED THIS 15th DAY OF March 2024

[Signature]
 BERLIN TWP., ZONING INSPECTOR

APPROVED THIS 26th DAY OF March 2024

[Signature]
 DELCO-CO WATER CO., INC.

APPROVED THIS _____ DAY OF _____ 20____

DELAWARE COUNTY SANITARY ENGINEER

APPROVED THIS _____ DAY OF _____ 20____

DELAWARE COUNTY ENGINEER

APPROVED THIS _____ DAY OF _____ 20____

DIRECTOR, DELAWARE COUNTY
 REGIONAL PLANNING COMMISSION

THIS _____ DAY OF _____ 20____

DRIVES HEREIN DEDICATED TO PUBLIC USE ARE HEREBY APPROVED FOR THE COUNTY OF DELAWARE, STATE OF OHIO. STREET IMPROVEMENTS WITHIN SAID DEDICATED RIGHT-OF-WAY SHALL NOT BE ACCEPTED FOR PUBLIC USE AND/OR MAINTENANCE UNLESS AND UNTIL CONSTRUCTION IS COMPLETED AND STREETS ARE FORMALLY ACCEPTED BY DELAWARE COUNTY.

DELAWARE COUNTY COMMISSIONERS

TRANSFERRED THIS _____ DAY OF _____ 20____

AUDITOR, DELAWARE COUNTY, OHIO

RECORDED THIS _____ DAY OF _____ 20____

RECORDER, DELAWARE COUNTY, OHIO

AT _____: _____ A.M./P.M.

IN BOOK _____, PAGE(S) _____;

PLAT CABINET _____, SLIDE _____, FEE \$ _____

DRAINAGE MAINTENANCE PETITION RECORDED IN THE DELAWARE COUNTY COMMISSIONER'S JOURNAL, RESOLUTION NO. _____, JOURNAL DATE _____

BASIS OF BEARING

THE BASIS OF BEARING SHOW HEREON IS BASED ON NAD83 (2011), OHIO STATE PLANE NORTH ZONE.

SOURCE OF DATA

THE SOURCES OF RECORDED SURVEY DATA REFERENCED IN THE PLAN AND TEXT OF THIS PLAT ARE THE RECORDS OF THE RECORDER'S OFFICE, DELAWARE COUNTY, OHIO.

IRON PINS

ALL IRON PINS SET ARE SOLID 5/8" REBAR WITH A CAP MARKED "CESO". MONUMENTS SHALL BE SET UPON COMPLETION OF CONSTRUCTION.

PERMANENT MARKERS

ALL IRON PINS SET ARE SOLID IRON PINS, 1" IN DIAMETER, WITH AN ALUMINUM CAP STAMPED "CESO". MONUMENTS SHALL BE SET UPON COMPLETION OF CONSTRUCTION.

CERTIFICATION

WE DO HEREBY CERTIFY THAT WE HAVE SURVEYED THE ATTACHED PREMISES, PREPARED THE ATTACHED PLAT, AND THAT SAID PLAT IS CORRECT. ALL DIMENSIONS ARE SHOWN IN FEET AND DECIMAL PARTS THEREOF. DIMENSIONS SHOWN ALONG CURVES ARE CHORD MEASUREMENTS. PERMANENT MARKERS, MAGNETIC NAILS AND IRON PINS ARE TO BE PLACED AS SHOWN UPON COMPLETION OF CONSTRUCTION NECESSARY TO THE IMPROVEMENTS OF THIS LAND. FIELD WORK WAS COMPLETED IN JUNE 2022.

[Signature] 3-18-24
 SURVEYED AND PLATTED BY: CESO INC.
 JEFFREY MILLER, P.S.
 OHIO P.S. NO. 7211
 2800 CORPORATE EXCHANGE DRIVE, SUITE 400
 COLUMBUS, OHIO 43231



ACREAGE BREAKDOWN	
TOTAL ACREAGE:	16.897
ACREAGE IN RIGHT OF WAY	2.424
ACREAGE IN OPEN SPACE (LOTS 3582 & 3583)	4.749
ACREAGE IN BUILDABLE LOTS (29)	9.724

ACREAGE BREAKDOWN	
ACREAGE IN BERLIN TOWNSHIP	16.897
TOTAL ACREAGE:	16.897

ACREAGE BREAKDOWN:	
FARM LOT 9	16.897

PLAT	
BERLIN BLUFFS SECTION 2	
BERLIN TOWNSHIP DELAWARE COUNTY, OHIO	
SCALE: N/A	DATE: 2/24/2023
DESIGN: N/A	JOB NO.: 760321
DRAWN: OPG	SHEET NO.:
CHECKED: ALB	1 OF 4

BERLIN BLUFFS SECTION 2

STATE OF OHIO, DELAWARE COUNTY, BERLIN TOWNSHIP
 FARM LOT 9, SECTION 3, TOWNSHIP 4, RANGE 18,
 UNITED STATES MILITARY LANDS

NOTE "A": NOTICE IS HEREBY GIVEN TO ANY BUYER OF THE LOTS DELINEATED UPON THIS PLAT, THAT ON FILE WITH THE BUILDING DEPARTMENT OF DELAWARE COUNTY, ARE SITE IMPROVEMENTS PLANS FOR THE DEVELOPMENT OF SAID LOTS SHOWING PROPOSED LOT DRAINAGE, PROPOSED GROUND ELEVATION AT HOUSE AND/OR LOT GRADING PLANS. THESE PLANS, AS APPROVED BY THE GOVERNMENTAL AGENCIES, ARE CONSIDERED PART OF THE APPROVAL OF THIS SUBDIVISION AND ARE TO BE INCORPORATED INTO THE FINAL PLOT PLAN REQUIRED WITH THE BUILDING PERMIT.

NOTE "B": BERLIN TOWNSHIP ZONING CODE FOR "BERLIN BLUFFS SECTION 2". IN EFFECT AT TIME OF PLATTING OF "BERLIN BLUFFS SECTION 2", SPECIFIES THE FOLLOWING SETBACK REQUIREMENTS:

DESIGNATION	R-3 WITH PRD OVERLAY
FRONT YARD:	30 FEET
SIDE YARD:	12.5 FEET
REAR YARD:	25 FEET

NOTE "C": ACREAGE BREAKDOWN

TOTAL ACREAGE:	16.897
ACREAGE IN RIGHT OF WAY	2.424
ACREAGE IN OPEN SPACE (3582 & 3583)	4.749
ACREAGE IN BUILDABLE LOTS (29)	9.724

ACREAGE BREAKDOWN	
ACREAGE IN BERLIN TOWNSHIP	16.897
TOTAL ACREAGE:	16.897

ACREAGE BREAKDOWN:	
FARM LOT 9	16.897

NOTE "D": NON-EXCLUSIVE UTILITY EASEMENTS ARE PLATTED FOR THE CONSTRUCTION, OPERATION AND MAINTENANCE OF PUBLIC AND PRIVATE UTILITIES, STORM WATER MANAGEMENT, AND SERVICE CONNECTIONS THERETO, ABOVE AND BENEATH THE SURFACE OF THE GROUND.

NOTE "E": A NON-EXCLUSIVE EASEMENT IS HEREBY SPECIFICALLY GRANTED UNTO DEL-CO WATER COMPANY INC., ITS SUCCESSORS AND ASSIGNS, FOR THE LOCATION OF WATER LINES, VALVES AND APPURTENANCES WITHIN THE RIGHTS-OF-WAYS HEREBY DEDICATED AND WITHIN AREAS DESIGNATED HEREON AS "UTILITY EASEMENT", "SANITARY EASEMENT" OR "DRAINAGE EASEMENT" THAT ARE LOCATED ALONGSIDE THE RIGHTS-OF-WAY HEREBY DEDICATED. ALSO GRANTED IS THE RIGHT OF DEL-CO WATER COMPANY INC., TO INSTALL, SERVICE, AND MAINTAIN WATER METER CROCKS AND APPURTENANCES IN SAID EASEMENT AREAS ALONGSIDE SAID RIGHTS-OF-WAY. THE EASEMENT AREA SHALL BE FOR THE UNOBSTRUCTED USE OF DEL-CO WATER COMPANY, INC. PLACEMENT OF FENCES, WALLS, PILLARS, TREES, GARDENS, SHRUBBERIES, AND OTHER SURFACE FEATURES IS STRICTLY PROHIBITED.

NOTE "F": ON FILE WITH COUNTY ENGINEERING, BUILDING, HEALTH AND PLATTING AUTHORITIES ARE PLANS INDICATING THE NATURE AND LOCATION OF VARIOUS SUBDIVISION IMPROVEMENTS.

NOTE "G": BE ADVISED: A SUB-SURFACE DRAINAGE SYSTEM MAY EXIST ON THIS SITE. THE SYSTEM AND/OR OUTLET IF LOCATED ON THIS PROPERTY MUST BE MAINTAINED AT ALL TIMES.

NOTE "H": ZONING SETBACKS REFLECT CURRENT ZONING STANDARDS AT THE TIME OF THE ZONING INSPECTOR'S SIGNATURE OF THE FINAL PLAT AND ARE NOT SUBDIVISION PLAT RESTRICTIONS.

NOTE "I": NO VEHICULAR ACCESS TO BE IN EFFECT UNTIL SUCH TIME AS THE PUBLIC STREET RIGHT-OF-WAY IS EXTENDED BY PLAT, DEED, OR EASEMENT.

NOTE "J": AT THE TIME OF PLATTING AS "BERLIN BLUFFS SECTION 2", IS IN THE FLOOD HAZARD ZONE "X" (OUTSIDE OF THE 500-YEAR FLOODPLAIN) AS DESIGNATED AND DELINEATED ON THE FEMA FLOOD INSURANCE MAP FOR DELAWARE COUNTY, OHIO, AND INCORPORATED AREA, MAP NUMBER 39041C0232K, WITH EFFECTIVE DATE, OF APRIL 16, 2009 AND COMMUNITY PANEL NO. 39041C0255K (DATED APRIL 15, 2009).

NOTE "K": AT THE TIME OF PLATTING, ELECTRIC, CABLE AND TELEPHONE SERVICE PROVIDERS HAVE NOT ISSUED INFORMATION REQUIRED SO THAT EASEMENT AREAS, IN ADDITION TO THOSE SHOWN ON THIS PLAT AS DEEMED NECESSARY BY THESE PROVIDERS FOR THE INSTALLATION AND MAINTENANCE OF ALL OF THEIR MAIN LINE FACILITIES, COULD CONVENIENTLY BE SHOWN ON THIS PLAT. EXISTING RECORDED EASEMENT INFORMATION DESIRED ABOUT SUBDIVISION PLAT OF "BERLIN BLUFFS SECTION 2" PLAT OR ANY PART THEREOF CAN BE ACQUIRED BY A COMPETENT EXAMINATION OF THE THEN CURRENT PUBLIC RECORD, INCLUDING THOSE IN THE DELAWARE COUNTY RECORDER'S OFFICE.

NOTE "L": FOR ANY EASEMENT SHOWN ON THIS PLAT THAT CONTAINS A STORM SEWER, CULVERT, OVER LAND OPEN DITCH FLOOD ROUTE, DETENTION BASIN, RETENTION BASIN AND/OR OTHER STORM WATER STRUCTURE (HEREIN REFERRED TO AS STORM SEWER), THE STORM SEWER RIGHTS ARE SENIOR TO THE RIGHTS OF ANY OTHER PUBLIC OR PRIVATE UTILITY OR INTEREST UTILIZING THE EASEMENT, EXCEPT FOR OVERLAP AREAS WITH A "SANITARY EASEMENT". ANY COSTS ASSOCIATED WITH THE DAMAGE, REPAIR, REPLACEMENT OR RELOCATION OF ANY BURIED OR ABOVE GROUND FACILITY OR STRUCTURE THAT IS NECESSARY TO ALLOW THE MAINTENANCE, REPAIR OR REPLACEMENT OF THE STORM SEWER SHALL BE THE RESPONSIBILITY OF THE OWNER OF SAID UTILITY, FACILITY OR STRUCTURE. WHEN MAINTENANCE, REPAIR OR REPLACEMENT OF A STORM SEWER CAUSES THE REMOVAL OF ANY TREES, PLANTINGS, LANDSCAPING, FENCE, DRIVEWAY OR ANY OTHER FEATURE LOCATED WITHIN THE EASEMENT, THE REPLACEMENT AND COST OF SAID ITEMS SHALL BE THE RESPONSIBILITY OF THE OWNER OF THE UNDERLYING PROPERTY OR HOMEOWNER'S ASSOCIATION IF APPLICABLE.

NOTE "M": ANY LANDSCAPE FEATURES, SUCH AS TREES, FENCES, RETAINING WALLS, ETC. IN DRAINAGE EASEMENTS SHALL BE REVIEWED BY THE DELAWARE SOIL AND WATER CONSERVATION DISTRICT (DCWCD) AND THE DELAWARE COUNTY ENGINEER'S OFFICE (DCEO) PRIOR TO INSTALLATION. THE DSWCD AND DCEO WILL REVIEW THE PROPOSED IMPROVEMENTS TO ASSURE THAT THE IMPROVEMENTS TO ASSURE THAT THE IMPROVEMENTS WILL NOT INTERFERE WITH THE STORM WATER CONTROL FACILITIES.

NOTE "N": NO BUILDINGS, SHEDS, DECKS, POOLS, OR OTHER SUCH STRUCTURES, OR THE FOOTERS OR FOUNDATIONS OF ANY STRUCTURES OR FEATURES SHALL BE CONSTRUCTED ABOVE OR BELOW GROUND WITHIN THE LIMITS OF ANY DRAINAGE EASEMENT UNLESS SAID STRUCTURE IS APPROVED IN WRITING BY THE DELAWARE COUNTY ENGINEER'S OFFICE.

NOTE "O": DRIVES SHALL NOT ENCROACH INTO ANY SIDE YARD DRAINAGE EASEMENT.

NOTE "P": ALL RESERVE/OPEN SPACES DELINEATED ON THIS PLAT SHALL BE ACCESSIBLE TO DELAWARE COUNTY, ITS SUCCESSORS AND ASSIGNS, FOR DRAINAGE MAINTENANCE PURPOSES.

NOTE "Q": SANITARY EASEMENTS ARE SOLELY FOR CONSTRUCTION, OPERATION, AND MAINTENANCE OF PUBLIC AND OR PRIVATE SANITARY SEWERS, SERVICE CONNECTIONS, MANHOLES, FORCE MAINS, VALVES, AND OTHER SANITARY APPURTENANCES. SANITARY EASEMENTS MAY BE CROSSED BY OTHER UTILITIES AS EXPRESSED HEREIN.

NOTE "R": ALL EASEMENTS AND RESERVES THAT OVERLAP OR COVER ALL OR PORTIONS OF A "SANITARY EASEMENT" SHALL BE SUBJECT TO THE PROVISIONS OF THE "SANITARY EASEMENT" WITHIN THE OVERLAP OR COVER AREAS. WORK TO FACILITATE SURFACE WATER DRAINAGE WITHIN THE OVERLAP OR COVER AREAS IS NOT RESTRICTED; HOWEVER ANY PROPOSED NEW STORM SEWER PIPES, INLETS, CATCH BASINS, STRUCTURES, OR OTHER STORM WATER APPURTENANCES OR INFRASTRUCTURE FEATURES SUBSEQUENT TO THOSE WHICH WERE PERMITTED WITH THE ORIGINAL SANITARY SEWER IMPROVEMENTS SHALL ONLY BE PERMITTED IF APPROVED BY THE GOVERNING STORMWATER AUTHORITY AND THE DELAWARE COUNTY SANITARY ENGINEER.

NOTE "S": THE ADDITION OR REMOVAL OF ANY DIRT, SOIL, FILL, OR OTHER CHANGES TO THE GROUND ELEVATION ABOVE THE SANITARY SEWER OR FORCE MAIN AND/OR WITHIN THE SANITARY EASEMENT SHALL BE SUBJECT TO APPROVAL OF THE DELAWARE COUNTY SANITARY ENGINEER.

NOTE "T": THE DELAWARE COUNTY SANITARY ENGINEER RESERVES THE RIGHT TO REQUIRE THAT ALL EARTHWORK WITHIN THE SANITARY EASEMENT BE GRADED TO SUCH A LEVEL THAT WILL, IN HIS OR HER OPINION, NOT JEOPARDIZE THE STRUCTURAL INTEGRITY OF, INFRINGE UPON, OR LIMIT THE COUNTY'S REASONABLE ACCESS TO THE SANITARY SEWER OR FORCE MAIN.

NOTE "U": NO OTHER UTILITY LINES, CONDUITS, MAINS, VALVES, BOXES, PEDESTALS, TRANSFORMERS, OR OTHER UTILITY APPURTENANCES ARE PERMITTED WITHIN ANY SANITARY EASEMENT UNLESS THEY ARE APPROVED ON THE SIGNED SANITARY SEWER PLANS, OR OTHERWISE APPROVED IN WRITING BY THE DELAWARE COUNTY SANITARY ENGINEER, EXCEPT THAT THE RIGHTS GRANTED TO DELCO WATER COMPANY, ITS SUCCESSORS, AND ASSIGNS TO INSTALL, SERVICE AND MAINTAIN RESIDENTIAL WATER SERVICES, METER CROCKS AND APPURTENANCES AS DESIGNATED ON THIS PLAT ARE NOT RESTRICTED.

NOTE "V": OTHER UTILITY CROSSINGS WITHIN THE SANITARY EASEMENT ARE ONLY PERMITTED AS DESCRIBED HEREIN, UNLESS THEY ARE APPROVED ON THE SIGNED SANITARY SEWER PLANS OR OTHERWISE APPROVED IN WRITING BY THE DELAWARE COUNTY SANITARY ENGINEER. RIGHT ANGLE OR NEAR RIGHT ANGLE UTILITY CROSSINGS ("NEAR RIGHT ANGLE" IS DEFINED AS AN ANGLE BETWEEN EIGHTY (80) DEGREES AND ONE-HUNDRED (100) DEGREES) OVER, ACROSS, OR UNDER A SANITARY SEWER OR FORCE MAIN AND OVER, ACROSS, UNDER, OR THROUGH THE SANITARY EASEMENT ARE NOT HEREBY RESTRICTED, EXCEPT THAT ALL UTILITY CROSSINGS UNDER A SANITARY SEWER OR FORCE MAIN SHALL BE SUBJECT TO THE REVIEW AND APPROVAL OF THE DELAWARE COUNTY SANITARY ENGINEER.


NOTE "W": ANY LANDSCAPING FEATURES, SUCH AS, BUT NOT LIMITED TO, TREES, FENCES, SIGNS STACKABLE RETAINING WALLS, ETC., WITHIN THE SANITARY EASEMENT SHALL BE REVIEWED FOR APPROVAL BY THE DELAWARE COUNTY SANITARY ENGINEER PRIOR TO INSTALLATION.

NOTE "X": WHEN MAINTENANCE, REPAIR OR REPLACEMENT OF PUBLIC SANITARY SEWERS, MANHOLES, FORCE MAINS, VALVES, AND OTHER PUBLIC SANITARY APPURTENANCES CAUSES THE REMOVAL OF ANY TREES, PLANTINGS, LANDSCAPING, FENCE, OR ANY OTHER FEATURE LOCATED WITHIN THE SANITARY EASEMENT, WITH THE EXCEPTION OF DRIVEWAYS AND PEDESTRIAN PATHWAYS, THE REPLACEMENT AND COST OF SAID ITEMS SHALL BE THE RESPONSIBILITY OF THE OWNER OF THE UNDERLYING PROPERTY OR HOMEOWNER'S ASSOCIATION IF APPLICABLE.

NOTE "Y": LOTS 3582 & 3583 AS NUMBERED AND DELINEATED HEREON, SHALL BE OWNED AND MAINTAINED BY AN ASSOCIATION COMPRISED OF THE OWNERS OF THE FEE SIMPLE TITLES TO THE PLATTED LOTS SHOWN HEREON FOR THE PURPOSE OF COMMON OPEN SPACE AND STORM RUN-OFF FACILITIES; ALL OF LOTS 3582 & 3583 ARE DESIGNATED AS OPEN SPACE.



NOTE "Z": WITHIN THOSE AREAS OF LAND DESIGNATED "DRAINAGE EASEMENT" ON THIS PLAT, AN ADDITIONAL EASEMENT IS HEREBY RESERVED FOR THE PURPOSE OF CONSTRUCTING, OPERATING AND MAINTAINING MAJOR STORM WATER DRAINAGE SWALES AND/OR OTHER STORM WATER DRAINAGE FACILITIES. NO ABOVE GRADE STRUCTURES, DAMS, OR OTHER OBSTRUCTIONS TO THE FLOWS OF STORM WATER RUNOFF ARE PERMITTED WITHIN DRAINAGE EASEMENT AREAS AS DELINEATED ON THIS PLAT. EASEMENT AREAS SHOWN HEREON OUTSIDE OF THE PLATTED AREA ARE WITHIN LANDS OWNED BY THE UNDERSIGNED AND EASEMENTS ARE HEREBY RESERVED THEREIN FOR THE USE AND PURPOSES EXPRESSED HEREIN.

NOTE "AA": WITHIN THOSE AREAS OF LAND DESIGNATED "DRAINAGE EASEMENT", AN EASEMENT IS HEREBY RESERVED FOR MAINTAINING STORM WATER DRAINAGE SWALES AND/OR OTHER STORM WATER DRAINAGE FACILITIES ALONG WITH GRANTING DELAWARE COUNTY, ITS SUCCESSORS OR ASSIGNS THE RIGHT OF INGRESS OR EGRESS FROM THE PUBLIC RIGHT-OF-WAY TO THE DRAINAGE EASEMENT AS DEFINED ABOVE. PURSUANT TO ORC SECTION 6137, DELAWARE COUNTY, ITS SUCCESSORS OR ASSIGNS, SHALL TAKE CORRECTIVE MEASURES OR REPAIRS TO RESTORE THE CULVERT AND/OR WATER COURSE, IF NECESSARY, INCLUDING THOSE ACTIONS CAUSED BY AN EMERGENCY SITUATION. THE COSTS ASSOCIATED WITH THESE CORRECTIVE MEASURES SHALL BE ASSESSED BY THE OWNER(S).

PLAT	
BERLIN BLUFFS SECTION 2	
BERLIN TOWNSHIP	DELAWARE COUNTY, OHIO
SCALE: N/A	DATE: 2/24/2023
DESIGN: N/A	JOB NO.: 760321
DRAWN: OPG	SHEET NO.: 2 OF 4
CHECKED: ALB	
 WWW.CESOINC.COM	

BERLIN BLUFFS SECTION 2

STATE OF OHIO, DELAWARE COUNTY, BERLIN TOWNSHIP
 FARM LOT 9, SECTION 3, TOWNSHIP 4, RANGE 18,
 UNITED STATES MILITARY LANDS



- CESO LEGEND**
- IRON PIN FOUND
 - IRON PIN TO BE SET (5/8"x30" REBAR W/ CESO CAP)
 - ▲ MAG NAIL SET
 - PERMANENT MARKER SET (1"x30" REBAR W/ ALUMINUM CESO CAP)
 - FENCE POST FOUND



SEE SHEET 4

PLAT	
BERLIN BLUFFS SECTION 2	
BERLIN TOWNSHIP DELAWARE COUNTY, OHIO	
SCALE: 1"=60'	DATE: 2/24/2023
DESIGN: N/A	JOB NO.: 760321
DRAWN: OPG	SHEET NO.: 3 OF 4
CHECKED: ALB	



BERLIN BLUFFS SECTION 2

STATE OF OHIO, DELAWARE COUNTY, BERLIN TOWNSHIP
 FARM LOT 9, SECTION 3, TOWNSHIP 4, RANGE 18,
 UNITED STATES MILITARY LANDS



CURVE TABLE				
CURVE	RADIUS	ARC LENGTH	CHORD	DELTA ANGLE
C1	280.00'	11.90'	S52° 17' 54"W, 11.90'	2° 26' 04"
C2	250.00'	240.86'	N81° 06' 58"E, 231.65'	55° 12' 05"
C3	250.00'	66.73'	S78° 55' 48"E, 66.53'	15° 17' 37"
C4	280.00'	78.71'	N61° 34' 06"E, 78.45'	16° 06' 21"
C5	280.00'	72.46'	N77° 02' 06"E, 72.26'	14° 49' 38"
C6	280.00'	72.46'	S88° 08' 16"E, 72.26'	14° 49' 38"
C7	280.00'	46.14'	S76° 00' 13"E, 46.08'	9° 26' 27"
C8	220.00'	45.29'	S77° 10' 48"E, 45.21'	11° 47' 39"
C9	220.00'	13.44'	S84° 49' 37"E, 13.44'	3° 29' 58"
C10	18.50'	28.97'	S48° 33' 46"W, 26.10'	89° 43' 16"
C11	18.50'	29.15'	S41° 26' 14"E, 26.23'	90° 16' 44"
C12	280.00'	7.92'	S85° 45' 59"E, 7.92'	1° 37' 14"
C13	280.00'	66.82'	S78° 07' 11"E, 66.66'	13° 40' 23"
C14	220.00'	211.96'	N81° 06' 58"E, 203.85'	55° 12' 05"

LINE TABLE		
LINE #	DIRECTION	LENGTH
L1	S27° 16' 37"E	14.61
L2	S62° 43' 23"W	122.97
L3	N86° 34' 36"W	240.00
L4	S18° 43' 01"W	101.70
L5	N18° 43' 01"E	99.01
L6	N73° 43' 02"W	163.09
L7	S87° 05' 15"W	231.61
L8	N34° 48' 36"W	66.92
L9	N54° 58' 07"W	15.90
L10	N04° 34' 39"W	49.61
L11	N25° 52' 35"W	48.79
L12	N35° 08' 46"W	16.21
L13	N34° 34' 23"W	51.19
L14	N40° 34' 38"W	54.84
L15	N47° 08' 43"W	50.91
L16	N44° 41' 37"W	47.75
L17	N40° 45' 02"W	32.93

SEE SHEET 3

- CESO LEGEND**
- IRON PIN FOUND
 - IRON PIN TO BE SET (5/8"x30" REBAR W/ CESO CAP)
 - ▲ MAG NAIL SET
 - PERMANENT MARKER SET (1"x30" REBAR W/ ALUMINUM CESO CAP)
 - FENCE POST FOUND

PLAT	
BERLIN BLUFFS SECTION 2	
BERLIN TOWNSHIP DELAWARE COUNTY, OHIO	
SCALE: 1"=60'	DATE: 2/24/2023
DESIGN: N/A	JOB NO.: 760321
DRAWN: OPG	SHEET NO.: 4 OF 4
CHECKED: ALB	

CESO
WWW.CESOINC.COM